



Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651
phone 208.466.7594 - fax 208.461.9505 - RCE-481
email: doug@nessllc.com - www.nessllc.com



Ness LLC Proposal for: 347 E. Eaglewoods Ln. Eagle, Idaho 83616

December 3, 2019

What to expect with a Drain Install and Remediation:

- ✓ Access is key! We will need admission Monday through Friday, 8 am - 5 pm while the project is in progress. Ness is bonded and insured. It is not necessary for a home owner to be present while the work is being done. Please make sure we have a house key or garage code for entry. The easier the access is for our technicians, the faster the job goes!

- ✓ All access to the crawlspace will be protected by plastic sheeting during work.


- ✓ Installing a drain system is a 14-21 day process, depending on drying time. The process CANNOT be rushed or our warranty may be compromised. Please plan accordingly.

- ✓ Mold remediation is usually a 7-14 day process, depending on dry times and 3rd party inspection scheduling.

- ✓ Fans need time to dry the area so we don't always schedule for consecutive days. We try to give as much notice as possible but last minute schedule changes can and do occur. Please direct all questions to ty@nessllc.com

- ✓ If a signed bid is returned in the next 24 hours, your estimated start date will be during the week of Dec. 16th.

- ✓ We have now extended our warranty for sump pump drainage systems to 10 years!





Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651
phone 208.466.7594 - fax 208.461.9505 - RCE-481
email: doug@nessllc.com - www.nessllc.com



Aubyn Jo Dean, 916-616-9401
aubynjo@yahoo.com

12-3-19

Page 2 of 3

PROPOSED WATER DRAINAGE for the crawlspace at 347 E. Eaglewoods Ln. Eagle, Idaho 83616
Ness, LLC is an IICRC council certified Mold Remediation Contractor, licensed, bonded, and insured with mold and environmental pollution endorsements

Because of the ongoing history of seasonal water intrusion, a two pump drain system is recommended. There was also some apparent microbial growth noted on the rim joist in sporadic areas that will need to be cleaned per IICRC guidelines. This is most likely because most of the foundation vents are blocked which prevents proper air flow. The vapor barrier is also in poor condition and will need to be replaced.

Part 1: Drainage (Digline will be contacted to mark all utilities)

1. All access to crawlspace surfaces will be protected by plastic sheeting during work.
2. Preliminary digging and pumping to remove excess water, as needed.
3. Negative air machine used for the crawlspace during work and for dry down.
4. Additional fans will be installed for dry down, as needed.
5. Clear foundation vents of any insulation that may be blocking air flow.

Part 2:

1. Install a fabric lined graded drain system below the bottom of the footings on the entire perimeter of the crawlspace except for behind the garage.
2. Drain in crawlspace will collect into two sump tanks. One tank will be located in the back area and the other will be in the left side of the crawlspace.

Part 3: Install sump pumps into tanks with insulated lids in the appropriate determined areas. Sumps will discharge through a drain line to a dispersal bed towards the front left landscaped area. (The sump pump discharge line will not be visible from the outside of the house. Installation of electrical outlet with audible alarm and manual shut-off included.)

Total Labor & Materials Parts 1-3 = \$4,860.38

Part 4: Mold Remediation

1. All access to the crawlspace will be protected during work.
2. Containment will be set at the crawlspace access.
3. The furnace system is to remain off during the work and for three hours after each treatment.
4. Hepa filtered negative air flow will be ongoing during the project
5. Remove any insulation from the area where work is to be performed.
6. Surface cleaning and abrasion removal, as needed and treat impacted rim joist. (See Part 5)
7. Push back insulation where removed.
8. Clear all vents of any insulation or debris that may be obstructing air flow.

Part 5: Microbial Growth Remediation per IICRC

After containment is set up, then surface cleaning and abrasive removal will be performed, as needed, of visible microbial growth on the impacted rim joist. Once mold impacted surfaces are cleaned, then treat the remediated surfaces in the crawlspace with a non-toxic Microbial Growth Inhibitor. Procedures are established from IICRC S520 Standard and Reference Guide for Professional Mold Remediation. (2) All work in the crawlspace will be performed using accepted procedures. (3) Respiratory Protection is in accordance with the OSHA respiratory protection standard (29 CFR 1910.134) for the remediation. Gloves, full-face respirators, p-100 particulate filters, Tyvek full body suits with hoods and boots. Photo documentation of work performed is available at the end of the project upon prior request. Disposal of debris.

Total Labor & Materials Parts 4-5 = \$1,687.12
(This discounted price is only good if done with the drain system)



Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651
phone 208.466.7594 - fax 208.461.9505 - RCE-481
email: doug@nessllc.com - www.nessllc.com



Aubyn Jo Dean, 916-616-9401

12-3-19

Page 3 of 3

Part 6: Recommended: 3rd Party Certified mold inspector's visual inspection and documentation.
Final Clearance Air Testing not included in protocol or scope

ADD to Total \$195.00

Part 7: Remove and dispose of old vapor barrier, miscellaneous debris, and building materials. Install new 6 mil. vapor barrier in the entire crawlspace and pull up onto the footings, where possible.

ADD to Total \$955.13

>> 50% down and 50% paid upon completion <<
>> 3% charge on credit card transactions <<

Parts 1-3 Accepted by: _____ Date _____

Parts 4-5 Accepted by: _____ Date _____

Part 6 Accepted by: _____ Date _____

Part 7 Accepted by: _____ Date _____

Print Name: _____

When accepted, please sign, fax or scan and send back. Fax 461-9505 or Email ty@nessllc.com
Douglas A. Ness (CMRS) -Idaho Contractor Registration# RCE-481

Ness, LLC gives a **10 Year Warranty** on sump pump, drain system for no standing water (as per signed contract) on the crawlspace floor where drain was installed from ground water seepage, and rain/snow. This Warranty is Transferable to new home buyer within warranty period. Drainage Warranty excludes water standing on the crawlspace floor from flooding that is not part of ground water seepage from irrigation or rain or due to, interior home appliances or plumbing leaks. Furthermore, Ness, LLC is not responsible for any future landscape changes that may disrupt the system. A Service Charge applies for *non-warranty* issues.

Work under this proposal is limited to the items listed. Any additional work will need to be outlined and set out by a separate contract, or have the contract amended and signed to reflect any additional work desired.

Ness LLC give a **5 year limited warranty** on no visible microbial re-growth where work is done. Warranty is **void** if any water or water source introduced into the area.

Work under this proposal is limited to the items listed. Any additional work will need to be outlined and set out by a separate contract, or have the contract amended and signed to reflect any additional work desired.