



# Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651  
phone 208.466.7594 - fax 208.461.9505 - RCE-481  
email: [doug@nessllc.com](mailto:doug@nessllc.com) - [www.nessllc.com](http://www.nessllc.com)



**Ness LLC Proposal for:** 2012 Arthur St. Caldwell, Idaho 83605

**February 10, 2020**

## **What to expect with a Mold Remediation Project:**

- ✓ Access is key! We will need admission Monday through Friday, 8 am - 5 pm while the project is in progress. Ness is bonded and insured. It is not necessary for a home owner to be present while the work is being done. If you are comfortable with it, please make sure we have a house key or garage code for entry. The easier the access is for our technicians, the faster the job goes!
  
- ✓ All access to the affected areas will be protected by plastic sheeting during work.
  
- ✓ Mold remediation will typically take 5-7 days and sometimes 5-10 working days, depending on the scope of work and scheduling.
  
- ✓ We don't always schedule for consecutive days. This is a normal part of our process. Fans may need to run an extra day or two to dry down surfaces and atmosphere.
  
- ✓ Please note that we are almost two weeks out in starting new projects. If signed and returned today, you will have an estimated start date around the 27th of February.





# Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651  
phone 208.466.7594 - fax 208.461.9505 - RCE-481  
email: doug@nessllc.com - www.nessllc.com



Jerry Hardy, 208-559-2398  
jbdebh@gmail.com

02-10-2020

Page 2 of 2

## RESTORATION PROPOSAL for the Attic at 2012 Arthur St. Caldwell, Idaho 83605

Ness, LLC is an IAQA council certified Mold Remediation Contractor, licensed, bonded, and insured with mold and environmental pollution endorsements.

As requested, the attic was inspected for microbial growth. Remediation is recommended as there is visible mold on the skip sheathing and top cords. Owner is to make sure all fans are ducted to vent to the exterior.

### Part 1:

1. All access to the attic will be protected during work.
2. The furnace/AC system is to remain off during the work and for 3 hours after treatment.
3. Establish negative air flow. This will be ongoing while the work is performed.
4. Surface cleaning and abrasion removal, as needed and treat impacted skip sheathing and top cords. **(See Part 2)**
5. Seal all penetrations that are accessible.

### Part 2: Microbial Growth Remediation

1. After containment is set up, then surface cleaning and abrasive removal as needed of visible microbial growth on the impacted skip sheathing and top cords. Once mold impacted surfaces are cleaned, then treat the remediated surfaces in the attic with a non-toxic Microbial Growth Inhibitor.
2. (1) Procedures are established from IICRC S520 Standard and Reference Guide for Professional Mold Remediation. (2) All work in the attic will be performed using accepted procedures. (3) Respiratory Protection is in accordance with the OSHA respiratory protection standard (29 CFR 1910.134) for the remediation. Gloves, full-face respirators, p-100 particulate filters, Tyvek full body suits with hoods and boots.
3. Photo documentation of work performed is available at the end of the project upon request. Disposal of debris.

**Total Labor & Materials: ----- Parts 1 - 2 = \$2,487.13**

**Part 3: Mandatory 3<sup>rd</sup> Party Certified mold inspector's visual inspection and documentation for the attic.**

**\*\*Final Clearance Air Testing not included in protocol or scope\*\***

**ADD to Total \$210.00**

*>> Paid out of closing as long as closing is within 21 days of job completion or 50% down and 50% paid upon completion <<  
>> 3% charge on credit card transactions <<*

Parts 1-2 Accepted by: \_\_\_\_\_ Date \_\_\_\_\_

Part 3 Accepted by: \_\_\_\_\_ Date \_\_\_\_\_

Please Indicate Payment Schedule: (check option) 50/50  Out of Closing

Please print name: \_\_\_\_\_

When accepted, please sign, fax or scan and send back to fax 461-9505 or [ty@nessllc.com](mailto:ty@nessllc.com)  
Douglas A. Ness (CMRS) -Idaho Contractor Registration# RCE-481

Ness LLC give a **5 year limited warranty** on no visible microbial re-growth where work is done. Warranty is void if any water or water source introduced into the area.

**Work under this proposal is limited to the items listed. Any additional work will need to be outlined and set out by a separate contract, or have the contract amended and signed to reflect any additional work desired.**