



Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651
phone 208.466.7594 - fax 208.461.9505 - RCE-481
email: doug@nessllc.com - www.nessllc.com



Tresidio Homes
dallin@tresidio.com

5-6-2020

Page 1 of 1

RESTORATION PROPOSAL for the crawlspace at 1421 N. Glen Aspen Ave. Star, LP27-2

Ness, LLC is an IICRC council certified Mold Remediation Contractor, licensed, bonded, and insured with mold and environmental pollution endorsements.

There appears to be sporadic mold growth on the floor joists and pony walls. This was likely caused by the furnace blowing into the crawlspace without the vapor barrier installed. Remediation will be needed. Please note that once remediated, new mold will not grow unless there is a water source introduced. (See warranty in the footer of the proposal)

Part 1: Mold Remediation

1. All access to crawlspace will be protected during work.
2. Containment will be set at the crawlspace access.
3. Hepa filtered negative air flow will be ongoing during the project.
4. The HVAC/AC system is to remain off during the work and for 4 hours after each treatment.
5. Remove insulation in the area where work is to be done, if necessary.
6. Surface cleaning and abrasive removal as needed of visible microbial growth on the impacted floor joists and pony walls.
(See Part 2)
7. Put back existing insulation, as needed.
8. Clear all air vents of insulation and/or debris

Part 2: Microbial Growth Remediation

1. After containment is set up, then perform surface cleaning and abrasive removal as needed of visible microbial growth on the impacted floor joists and pony walls. Once all visible mold is removed from impacted surfaces and inspected then do the final treatment of the remediated surfaces in the crawlspace with a non-toxic Microbial Growth inhibitor.)
2. (1) Procedures are established from IICRC S520 Standard and Reference Guide for Professional Mold Remediation. (2) All work in the crawlspace will be performed using accepted procedures. (3) Respiratory Protection is in accordance with the OSHA respiratory protection standard (29 CFR 1910.134) for the remediation. Gloves, full-face respirators, p-100 particulate filters, Tyvek full body suits with hoods and boots.
3. Photo documentation of work performed is available at the end of the project upon prior request. Disposal of debris.

Total Labor & Materials Parts 1-2 = \$1,950.00

Part 3: Recommended: 3rd Party Certified mold inspector's visual inspection and documentation.

****Final Clearance Air Testing not included in protocol or scope****

ADD to Total \$185.00

Part 4: Tresidio will install vapor barrier upon completion of remediation.

*>> To be paid in full upon completion <<
>> 3% charge on credit card transactions <<*

Parts 1-2 Accepted by: _____ Date _____

Part 3 Accepted by: _____ Date _____

Part 4 Accepted by: _____ Date _____

Please print name: _____

Douglas A. Ness (CMRS) -Idaho Contractor Registration# RCE-481

Ness LLC gives a **5 year limited warranty** on no visible microbial re-growth where work is done. Warranty is **void** if any water or water source introduced into the area. Failure to properly install the vapor barrier may void the warranty.

Work under this proposal is limited to the items listed. Any additional work will need to be outlined and set out by a separate contract, or have the contract amended and signed to reflect any additional work desired.