



Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651
phone 208.466.7594 - fax 208.461.9505 - RCE-481
email: doug@nessllc.com - www.nessllc.com



Randy Flynn, 303-517-3999
imrflynn@gmail.com

7-27-2020

Page 1 of 1

PROPOSED Drywell at 4038 W. Greenspire Dr. Meridian, Idaho 83646

See the requested bid below to remove the sump pump and connect the existing drain system to a drywell.

Part 1: Replace Sump Pump with Drywell

1. Digline will be contacted to mark utilities.
2. Remove existing sump pump and sump tank.
3. Backfill tank hole
4. Cancel current discharge and seal
5. Dig new drain under the footing and connect to interior trenches.
6. Drain will be graded and connected to an exterior drywell on the other side of the foundation from the original pump location.
7. Connect trenching to drywell: (Back left corner)
 - i. Excavate pit down to drainable soils or 8ft deep with sucker truck.
 - ii. Line pit and install 8" access pipe.
 - iii. Backfill with rock
 - iv. Lid to be installed on pipe at the surface for easy access
8. Ness is not responsible for any landscaping except for hauling away excess soil, as needed

Total Labor & Materials Part 1 = \$4,837.20

*****If signed within 24 hours, your estimated start date will be some time during the week of Sept. 14th.**

*50% down and 50% paid upon completion
>> 3% charge on credit card transactions <<*

Part 1 Accepted by: _____ **Date** _____

Please print name: _____
Douglas A. Ness (CMRS) -Idaho Contractor Registration# RCE-481

Work under this proposal is limited to the items listed. Any additional work will need to be outlined and set out by a separate contract, or have the contract amended and signed to reflect any additional work desired.