



Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651
phone 208.466.7594 - fax 208.461.9505 - RCE-481
email: doug@nessllc.com - www.nessllc.com



Todd Haynes, 208-340-3770
toddhaynes@gmail.com

11-6-2020

Page 1 of 1

PROPOSED Drywell at 3423 Mountain View Dr. Boise, Idaho

Part 1: Install drywell in window well of basement

When we start, the existing conditions of the landscape will be photo documented for conditions of the surfaces where we will work. Please note: There may be discovery, once excavation is performed, that is beyond this scope of work. At that time, all work will stop until a change order is drawn up and signed.

1. Digline will be contacted to mark utilities.
2. Excavated front window well next to the hose bib and expose basement wall.
3. Seal exposed portion of wall.
4. Sucker truck will suck out a pit in the bottom of the window well up to 8 ft deep from the bottom of the windowsill.
5. Install drywell.
 - i. Line pit with fabric and install 8" access pipe.
 - ii. Backfill with cinders and top with gravel that is like the existing gravel.
 - iii. Lid to be installed on pipe at the surface for easy access
6. Ness is not responsible for any landscaping.
7. Haul away excess soil if not needed.

Total Labor & Materials Part 1: \$3,768.12

*50% down and 50% paid upon completion
>> 3.5% charge on credit card transactions <<*

Part 1 Accepted by: _____ Date _____

Please print name: _____

Douglas A. Ness (CMRS) -Idaho Contractor Registration# RCE-481

Work under this proposal is limited to the items listed. Any additional work will need to be outlined and set out by a separate contract, or have the contract amended and signed to reflect any additional work desired.