



Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651
phone 208.466.7594 - fax 208.461.9505 - RCE-481
email: doug@nessllc.com - www.nessllc.com



Josh Kling, 208-941-9011
joshakling@gmail.com

5-28-2021

Page 1 of 1

RESTORATION PROPOSAL for the Crawlspace at 7625 E. Locust Lane Nampa, Idaho

Ness, LLC is an IICRC council certified Mold Remediation Contractor, licensed, bonded, and insured with mold and environmental pollution endorsements.

As requested, the crawlspace was inspected for mold under the new addition. Remediation will be necessary as there appears to be sporadic microbial growth on the floor decking and floor joists. We will also need to install new vapor barrier.

Part 1: Crawl Space Remediation

1. All access to the crawlspace will be protected during work.
2. Containment will be set at the crawlspace access.
3. Hepa filtered negative air flow will be ongoing during the project.
4. The furnace system is to remain off during the work and for, at least, 3 hours after each treatment.
5. Perform surface cleaning and abrasive removal, as needed, of visible microbial growth on the floor decking and floor joists in the crawlspace. (See Part 2)
6. Clear all foundation vents of any insulation or debris that may be obstructing air flow.

Part 2: Microbial Growth Remediation

1. After containment is set up, perform surface cleaning and abrasive removal, as needed, of visible microbial growth on the impacted floor decking and joists. Once mold impacted surfaces are cleaned, then treat the remediated surfaces in the crawlspace with a non-toxic Microbial Growth Inhibitor.
2. (1) Procedures are established from IICRC S520 Standard and Reference Guide for Professional Mold Remediation. (2) All work in the crawlspace/basement will be performed using accepted procedures. (3) Respiratory Protection is in accordance with the OSHA respiratory protection standard (29 CFR 1910.134) for the remediation. Gloves, full-face respirators, p-100 particulate filters, Tyvek full body suits with hoods and boots.
3. Photo documentation of work performed is available at the end of the project upon request. Disposal of debris.

Total Labor & Materials Parts 1-2: \$2,208.16

Part 3: Recommended: 3rd Party Certified mold inspector's visual inspection and documentation for the crawl space.

****Final Clearance Air Testing not included in protocol or scope****

ADD to Total: \$195.00

Part 4: Remove and dispose of old vapor barrier, miscellaneous debris, and building materials. Install new 6 mil. vapor barrier in the entire crawlspace. Plastic will be pulled up onto the footings, where possible.

ADD to Total: \$297.84

*>> 50% down, 50% due on completion <<
>> 3.5% charge on credit card transactions <<*

Parts 1-2 Accepted by: _____ Date _____

Part 3 Accepted by: _____ Date _____

Part 4 Accepted by: _____ Date _____

Douglas A. Ness (CMRS) -Idaho Contractor Registration# RCE-481

Ness LLC give a **5-year limited warranty** on no visible microbial re-growth where work is done. Warranty is **void** if any water or water source introduced into the area. **Work under this proposal is limited to the items listed. Any additional work will need to be outlined and set out by a separate contract, or have the contract amended and signed to reflect any additional work desired.**