



Ness LLC

1315 W. Orchard Ave, Nampa, ID 83651
phone 208.466.7594 - fax 208.461.9505 - RCE-481
email: doug@nessllc.com - www.nessllc.com



Jo Hedeman, 208-860-0978
jo@thehedemans.com

7-23-2021

Page 1 of 1

PROPOSED Drywell at 2329 E. Beatrice Dr. Meridian, Idaho

Ness, LLC is an IICRC council certified Mold Remediation Contractor, licensed, bonded, and insured with mold and environmental pollution endorsements.

It has been determined that the best option of moving the existing discharge line would be to connect it to a drywell. This will be located on the right side of the house and the line from the interior drain system will drain directly into the drywell.

Part 1: Install drywell on the right-side of the yard. (Digline will be contacted to mark utilities.)

1. All access to crawlspace surfaces will be protected by plastic sheeting during work.
2. Connect interior crawlspace trenching to drywell:
 - i. Excavate pit down to drainable soils or 9ft deep
 - ii. Line pit with fabric and install access pipe.
 - iii. Backfill with rock
 - iv. Lid to be installed on pipe at the surface for easy access
3. Ness is not responsible for any landscaping except for the gravel and soil in the trench. Owner will be responsible for replacing sod, as needed.
4. Haul away excess soil and sod, if not needed.

Total Labor & Materials Part 1 = \$5,371.08

Once signed we will need to call digline to locate utilities. This usually takes 3-4 days and then we can work this into the schedule.

***50% down and 50% paid upon completion
>> 3.5% charge on credit card transactions <<***

Part 1 Accepted by: _____ **Date** _____

Please print name: _____

Douglas A. Ness (CMRS) -Idaho Contractor Registration# RCE-481

Work under this proposal is limited to the items listed. Any additional work will need to be outlined and set out by a separate contract, or have the contract amended and signed to reflect any additional work desired.