



Pamela Tettis/Shawn Miller Smiller208@kw.com

7-16-2021

Page 1 of 1

RESTORATION PROPOSAL for the Crawlspace at 105 Queens Ct. Nampa, Idaho Ness, LLC is an IICRC council certified Mold Remediation Contractor, licensed, bonded, and insured with mold and environmental pollution endorsements.

As requested, the crawlspace was inspected for mold where there was a plumbing leak next to the entry hatch. Remediation will be necessary as there appears to be microbial growth on the floor decking and floor joist. Please note that moisture introduced to the area after remediation will void our warranty. We recommend consulting a plumber to evaluate the lines in the crawlspace.

Part 1: Crawl Space Remediation

- 1. All access to the crawlspace will be protected during work.
- 2. Containment will be set at the crawlspace access.
- 3. Hepa filtered negative air flow will be ongoing during the project.
- 4. The furnace system is to remain off during the work and for, at least, 3 hours after each treatment.
- 5. Surface cleaning and abrasive removal, as needed, of visible microbial growth on the floor decking and joist by the access hatch. (See Part 2)
- **6.** Clear all foundation vents of any insulation or debris that may be obstructing air flow.

Part 2: Microbial Growth Remediation

- 1. After containment is set up, perform surface cleaning and abrasive removal, as needed, of visible microbial growth on the impacted floor decking and joist. Once mold impacted surfaces are cleaned, then treat the remediated surfaces in the crawlspace with a non-toxic Microbial Growth Inhibitor.
- 2. (1) Procedures are established from IICRC S520 Standard and Reference Guide for Professional Mold Remediation. (2) All work in the crawlspace/basement will be performed using accepted procedures. (3) Respiratory Protection is in accordance with the OSHA respiratory protection standard (29 CFR 1910.134) for the remediation. Gloves, full-face respirators, p-100 particulate filters, Tyvek full body suits with hoods and boots.
- 3. Photo documentation of work performed is available at the end of the project upon request. Disposal of debris.

Total Labor & Materials Parts 1-2: \$829.32

Part 3: Recommended: 3rd Party Certified mold inspector's visual inspection and documentation for the attic and crawl space.

Final Clearance Air Testing not included in protocol or scope

ADD to Total: \$210.00

>> Paid out of closing if closing is within 21 days of job completion or 50% down and 50% paid upon completion << >> 3.5% charge on credit card transactions <<

Date
Date

